

**S.A. Comunale***An EMCOR Company***FIRE ALARM INSPECTION
& TEST REPORT**

BRANCH PHONE NUMBER: 740-383-6789



NATIONAL ACCOUNT NUMBER: 1-800-776-7181

DATE 10/08/2025 ADDITIONAL BUILDING DATA

SITE MARION TECHNICAL DOWNTOWN

CONTACT RONDA (CFO)

ADDRESS 107 N MAIN STREET

PHONE 740-725-4017

CITY MARION

STATE OH ZIP 43302

MONITORING ENTITY EMERGENCY 24

PHONE 800-877-3624

This inspection is: ☐ Annual ☐ Semi-Annual ☐ Quarterly ☐ Monthly ☐ Weekly ☒ Other SENSITIVITY

Type Transmission	☒ Digital	☐ Multiplex	☐ McCulloh	☐ Reverse Polarity	☐ RF	☐ Other
Panel Manufacturer	DMP	Model Number	XR2400F	Type	☒ Addressable	☐ Hard Wired

ALARM INITIATING DEVICES AND CIRCUIT INFORMATION

Qty of devices	Circuit Class	Type of device	Qty of devices	Circuit Class	Type of device
10	CLASS B	Manual Stations	1	CLASS B	Heat Detectors
0	NA	ION Detectors	0	NA	Waterflow Switches
5	CLASS B	Photo Detectors	0	NA	Supervisory Switches
0	NA	Duct Detectors			

ALARM NOTIFICATION APPLIANCES AND CIRCUIT INFORMATION

Qty of devices	Circuit Class	Type of device	Qty of devices	Circuit Class	Type of device
0	NA	Bells	0	NA	Strobes
23	CLASS B	Horns	0	NA	Horn/Strobes
0	NA	Speakers			
0	NA	Chimes			

SUPERVISORY SIGNAL-INITIATING DEVICES AND CIRCUIT INFORMATION

Qty of devices	Circuit Class	Type of device	Qty of devices	Circuit Class	Type of device
0	NA	Building Temp	0	NA	Generator or Controller Trouble
0	NA	Site Water Temp	0	NA	Generator Engine Running
0	NA	Site Water Level	0	NA	Generator in Auto Position
0	NA	Fire Pump Running	0	NA	Switch Transfer
0	NA	Fire Pump or Pump Controller Trouble			
0	NA	Fire Pump Power			
0	NA	Fire Pump Auto Position			

SIGNALING LINE CIRCUITS

Qty and Style (see NFPA 72, Table 6-6.1) of Signaling line circuits connected to system	Qty	2	Style(s)	B
---	-----	---	----------	---

SYSTEM POWER SUPPLIES

A. Primary (Main): Nominal Voltage	120vac	AMPS	20
Over Current Protection: Type	☒ Fuse ☐ Circuit Breaker	AMPS	30
Location (Primary Supply Panelboard)	NEXT TO PANEL	Disconnecting Means Location (Fuse or Breaker #)	1
B. Secondary (Standby): ☒ Storage Battery ☐ Other:	AMP HR Rating	12v/7ah	
Calculated capacity to operate system, in hours	☒ 24 ☐ 60 ☐ Other:		
☒ NA	Engine-Driven generator dedicated to fire alarm system. Location of fuel storage:		

TYPE BATTERY

☐ Dry Cell ☐ Nickel Cadmium ☒ Sealed Lead-Acid ☐ Lead-Acid ☐ Other:	
C. Emergency or standby system used as a backup to primary power supply, instead of using a secondary power supply.	
NA	Emergency system described in NFPA 70, Article 700
NA	Legally required standby described in NFPA 70, Article 701
NA	Optional standby system described in NFPA 70, Article 702, which also meets the performance requirements of Article 700 or 701

PRIOR TO ANY TESTING

Notifications Are Made	Yes	NA	No	Who	Time
Building Management	☒			STAFF	8:00am
Monitoring Entity	☒			EMERGENCY 24	8:00am
Other:					

SECONDARY POWER

Type	Visual	Functional	NA	Comments
Battery Condition	☒			-
Load Voltage		☒		-
Discharge Test		☒		-
Amp Hour Reading		☒		-
Specific Gravity			☒	-
Batteries Meet NFPA 72 Test Requirements:				☒ Yes ☐ No ☐ NA

INITIATING & SUPERVISORY DEVICE TESTS & INSPECTIONS
(ON SEPARATE FORM) - # OF PAGES ATTACHED EMERGENCY
COMMUNICATIONS EQUIPMENT 0

SYSTEM TESTS & INSPECTIONS

Type	Visual	Functional	NA	Comments	Type	Visual	Functional	NA	Comments
Control Panel		☒		PASS	Transient Suppressors			☒	
Interface Equipment		☒		PASS	Remote Annunciators		☒		PASS
Lamps/LEDS		☒		PASS	Audible			☒	
Fuses		☒		PASS	Visual			☒	
Primary Power Supply		☒		PASS	Speakers			☒	
Trouble Signals		☒		PASS	Voice Clarity			☒	
Disconnect Switches			☒		Door Holders			☒	
Ground Fault Monitor			☒		Door Unlock			☒	

Type	Visual	Functional	NA	Comments	Interface Equipment	Visual	Functional	NA	Comments
Phone Set			☒		Elevator Recall		☒		PASS
Phone Jack			☒		HVAC Shut Down			☒	
Off-Hook Indicator			☒		Specify:				
Amplifier(s)			☒		Special Hazards	Visual	Functional	NA	Comments
Tone Generators			☒		Specify:				
Call in Signal Silence			☒		Specify:				
System Performance			☒		Specify:				

SUPERVISING STATION MONITORING	Yes	NA	No	Time	Comments
Alarm Signal	☒			8:00am	-
Alarm Restoral	☒			10:00am	-
Trouble Signal	☒			8:00am	-
Trouble Restoral	☒			10:00am	-
Supervisory Signal		☒			-
Supervisory Restoral		☒			-

NOTIFIED TESTING COMPLETE	Yes	NA	No	Who	Time
Building Management	☒			STAFF	10:00am
Monitoring Entity	☒			EMERGENCY 24	10:00am
Other:					

HAS SENSITIVITY BEEN COMPLETED AS PER NFPA 72 OR LOCAL STATE CODES: YES ☒ NO ☐ NA ☐

Year Sensitivity Testing Completed: **2025**

Year Sensitivity Testing Due: **2027**

How Was Sensitivity Tested: **TRUTEST**

WHILE PERFORMING THE INSPECTION ADDITIONAL ITEMS WERE NOTED THAT NEED CORRECTED: YES ☐ NO ☐ NA ☒

☐ Explanation of "NO" answers, system deficiencies, and/or inspector recommendations are listed on SERVICE FOLLOW UP # _____, attached to this form.

☒ No SERVICE FOLLOW UP REPORT was required during this inspection.

I state that the information on this form is correct at the time and place of this inspection. All test and inspections were performed in accordance with applicable NFPA 72 test and inspection sections. All equipment tested at this time was left in operational condition upon completion of this inspection except as noted on any SERVICE FOLLOW UP REPORT as stated above.

Name of Inspector **Brandon Bickers**

Signature 

Certification # **54-70-1512**

I acknowledge that the inspection, deficiencies, and suggested improvements were discussed with me upon completion of the inspection. It is understood that all information contained herein is provided to the best of the knowledge of the person providing the information and that, if requested, will be forwarded to the authority having jurisdiction.

Name of Owner or Representative **Kevin**

Signature 

Are services required on Fire Alarm Components: ☐ YES ☒ NO How many devices this page require Service: N/A

S. A. Comunale Company Fire Alarm Inspection Report Rev 2.0 October 2019